



## GENERAL NOTES:

1. 12" OF SUB-BASE SHALL BE REMOVED AND REPLACED WITH 12" APPROVED SUB-BASE MATERIAL REMOVAL OF DELETERIOUS MATERIAL BELOW THE 12" WILL BE AT THE DISCRETION OF THE CITY ENGINEER

## SPECIFICATIONS

1. ALL MATERIALS SHALL MEET CITY OF MISSOULA SPECIFICATIONS. 564 LBS OF PORTLAND CEMENT PER CUBIC YARD OF CONCRETE SHALL BE USED.
2. OTHER APPLICABLE STANDARD DRAWING
  - A. NO. 740 - TYPE "L" CURB AND GUTTER
  - B. NO. 753 - TYPICAL SIDEWALK FOR DOWNTOWN
  - C. CONSTRUCTION TRAFFIC CONTROL PLANS



Engineering Division

### Typical Sidewalk Specifications Central Business District

Approved By  
City Engineer  
Kevin J. Slovarp

Adopted: 08/1989  
Revised: 04/03/2017

**STD - 754**